
WTR[®] Stop Gates and Lifting Beams Intake Dewatering and Maintenance





Stop Gates and Lifting Beams


WTR's Stop Gates and Lifting Beams are an essential component to support dewatering of intake structures for maintenance, inspection or isolation. Stop Gates, (AKA Stop Logs), are used in all types of applications where maintenance under dry conditions is required, inspection of the structure is necessary or a flow stream needs to be isolated. Applications include power plant raw water intakes (fossil and nuclear), industrial raw water, potable drinking water, irrigation and numerous other types of plants.

Unlike Sluice or Slide Gates, Stop Gates are unique. In lieu of being "fixed" and subjected to constant submergence and corrosion, (common with Sluice and Slide Gates), Stop Gates are stored above the water. Since most raw water intakes do not require frequent dewatering, Stop Gates are utilized only when required.

WTR Stop Gates are designed to provide superior sealing of intakes via a dedicated guide location and installation process. Our multi stage guide embedment process during construction of the intake assures proper fit and mating of the gates with the guides. Gates are installed with the water balanced on either side. When dewatering of the intake begins, the "on-seating head" will create a tight seal providing minimal or no leakage.

WTR Stop Gates are also designed to work in conjunction with a dedicated Lifting Beam, which allows for controlled engagement and disengagement of gate sections. This eliminates the need for divers in the water to connect and disconnect gate sections during insertion or removal. When inserted in the guide slot, the bias of the Lifting Beam will not allow disengagement of a gate section until properly seated, as confirmed by a sensing rod. When placed in the opposite bias, the Lifting Beam will engage with the upper most gate section for extraction.

Stop Gates can be supplied in single piece / full height configurations, multiple sections to reduce overhead lifting height or apron wall design to minimize gate height and quantity. Other options include balancing valves, dual direction guides, access ladders and above or below deck storage racks.




Stop Gate Optional Arrangements


Features:

- Stop Gates are built to site specific conditions, typically from 3ft. (1m) to 20ft. (6m) wide.
- Gates are normally supplied in Epoxy Coated Carbon Steel. Options for alternate materials are available.
- Each gate includes guidance rollers to prevent binding during insertion or removal under balanced water levels.
- Gates include side and bottom seals of high durometer neoprene for positive sealing.
- Designed for "on-seating head" to create an increasingly tighter seal to prevent leakage.
- Guides located in a dedicated slot, installed in a multi stage process to assure positive fit with Stop Gates.
- Guides are available in 316L SS, Duplex or Super Duplex and should be included in the intake cathodic protection system.
- Gate Lifting Beam accommodates submerged engagement and disengagement from gate sections.
- Lifting Beam operates in conjunction with sensing rod on gate to confirm seating prior to Lifting Beam disengagement.
- Lifting Beams are normally supplied in epoxy coated carbon steel. Options for alternate materials are available.


Options

- o Single piece / full height gates.
- o Multiple section gates to reduce required lifting height.
- o Apron wall design to minimize overall gate height and quantity of gates.
- o Balancing valves to allow for gravity refilling of intake.
- o Dual direction guides to accommodate sealing in either direction by reversing the gate.
- o Built in access ladders to allow for descending into the intake.
- o Storage racks located above the deck with access ladder or below the deck within a sump.





Above Deck Storage



Below Deck Storage

Stop Gate Sizing Data

(please complete for each channel width)

Plant / Site Name							
Site Location					(City, Stat	e, Country)	
Construction	New	Existing		New Expansion	Hazardous Area		
Water Source	Fresh Brackish Sea			Closed Cycle			
Number of Channels		Indoor		Outdoor	Cover	ed Area	
Flow Rate per Channel		GPM _		M³/sec _		MGD	
Channel Width (each)			Feet	·		Meters	
Deck Elevation or Depth			Feet			_ Meters	
Hi Water Elev. or Depth			Feet			Meters	
Low Water Elev. or Depth	Feet					Meters	
Invert / Bottom Elev.	Feet					Meters	
Desired Arrangement	One Pied	ce [Full H	eight Sec.	Apron Wall	Sec.	
Desired Options	Balancin	g Valves	Dual [Direction Guides	Access	Ladders	
Desired Storage Rack	Yes		Abov	e Deck	Below	Deck	
Desired Guide Materials	☐ 316L SS	Duple	ex SS	Super Duplex	Other .		
Desired Lift Beam Materials	CS Coate	ed 🗌 316L	SS	Duplex SS	Other		
Special Options							
CONTACT DETAILS							
Company Name							
Contact Person Name							
Email and Phone Number							



Represented by:

Tel: 801.713.9933 wtrengineering.com info@wtrengineering.com Salt Lake City, Utah, USA